



East Favel Bridge & Approach Roadworks

Ernst Hansch Construction (Hansch) was the successful bidder for the Manitoba Infrastructure contract for the construction of a new one span 45.2M x 13.2M precast prestressed concrete I-girder bridge on PTH #10 over the East Favel River in Minitonas, MB.

This project included the demolition, removal, dismantling and salvaging of the existing bridge prior to construction of the new bridge. Hansch utilized

silica fume concrete deck overlay for an extended life expectancy and a higher strength product. Temporary insulated enclosures and heating systems were used during the cold weather conditions to maintain the construction schedule. New asphalt approaches along with erosion control rip rap and landscaping completed the project.

Client	Manitoba Infrastructure
Location	PTH #10, Minitonas, Manitoba
Size	45.2 x 13.2 metre
Completed	2002
Project Type	Bridges & Infrastructure - New
Services	Design-Bid-Build



